BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/OW/WORK_INDENT12205

APPROVED SCHEDULE - B

Tender Notification No: No.EE/BTP/BBMP/E-PMT/19/2013-14, Date: 06.12.2013

Maintainence of Govt. School Buildings and Other Buildings in Ward No. 8, Kodigehalli Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of DANANJAYA B R	
				In Figures	In Words
1	9.9	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4169.27	Rupees Four Thousand One Hundred Sixty Nine and Twenty Seven Paise Only
2	14.6	Providing and constructing burnt brick masonry with approved quality of modular bricks of standard size of class designation 50 (table moulded) with cement mortar 1:6 for basement and superstructure including cost of materials, labour charges, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	5731.82	Rupees Five Thousand Seven Hundred Thirty One and Eighty Two Paise Only
3	0.51	Providing Sal wood frames of doors, windows, clerestory windows, ventilators, and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work.	Cum	65995.72	Rupees Sixty Five Thousand Nine Hundred Ninety Five and Seventy Two Paise Only
4	5.36	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 30mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work.	Sqm	3683.39	Rupees Three Thousand Six Hundred Eighty Three and Thirty Nine Paise Only
5	14.94	Providing and fixing in position fully glazed for windows shutters with Honne wood styles and rails of 25mm. thick, 75mm wide in single shutters with 4mm thick plain glass fixed with wooden beading including cost of materials, labour charges, HOM of machineries etc complete as per specifications and directions of engineer in charge of the work.	Sqm	2495.47	Rupees Two Thousand Four Hundred Ninety Five and Forty Seven Paise Only
6	205.88	Dismantling plastering and removing the debris with a lead upto 200m, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	17.84	Rupees Seventeen and Eighty Four Paise Only
7	205.88	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	161.61	Rupees One Hundred Sixty One and Sixty One Paise Only

8	111	Providing 20mm thick cement plaster in single coat with cement mortar 1:4, to stone masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. (Inside wall) etc complete as per specifications and directions of engineer in charge of the work.	Sqm	197.29	Rupees One Hundred Ninety Seven and Twenty Nine Paise Only
9	316.88	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	18.89	Rupees Eighteen and Eighty Nine Paise Only
10	181.56	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications (Out side Wall) etc complete as per specifications and directions of engineer in charge of the work.	Sqm	185.74	Rupees One Hundred Eighty Five and Seventy Four Paise Only
11	94.35	Flooring with 25mm to 40mm thick polished tandur blue stone slabs using mortar 1:6, 25mm thick over existing cement concrete bed or top of roof laid to line and level and jointed with cement slurry mixed with pigment to match the shade of the slab, including cost of materials, labour, curing, polishing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	1007.42	Rupees One Thousand Seven and Forty Two Paise Only
12	70.05	Providing and laying red oxide flooring 40mm thick with an under layer of 30mm thick 1:2:4 cement concrete, using broken granite metal of 12.5mm nominal size and top layer of 10mm thick plaster with 1:3 cement mortar mixed with red oxide (using b3.5 kg of red oxide per 50kg of cement) finished with floating coat of neat cement mixed with red oxide (mix of same proportion) including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	501.61	Rupees Five Hundred One and Sixty One Paise Only
13	316.88	Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. with Primer etc complete as per specifications and directions of engineer in charge of the work.	Sqm	78.71	Rupees Seventy Eight and Seventy One Paise Only
14	181.56	Providing and finishing external walls in tow coats with water proof cement paint of approve brand and shade to give an even shade after thourghly brooming the surface to remove all dirt and losse powdered material, free from mortar dops and other foreign matter cost of materials, labours, complete as per specifications with Primer etc complete as per specifications and directions of engineer in charge of the work.	Cum	77.66	Rupees Seventy Seven and Sixty Six Paise Only
15	131.1	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work.	Sqm	77.66	Rupees Seventy Seven and Sixty Six Paise Only
16	4	Hinges heavy Duty 5"	No	30.69	Rupees Thirty and Sixty Nine Paise Only

17	1	Door Lock	No	306.90	Rupees Three Hundred Six and Ninety Paise Only
18	4	MS Clamps	No	49.50	Rupees Forty Nine and Fifty Paise Only
19	2	Tower Bolt 300mm long	No	103.95	Rupees One Hundred Three and Ninety Five Paise Only
20	2	Handle (powder Coated) 150mm	No	61.38	Rupees Sixty One and Thirty Eight Paise Only
21	4	Brass Screws 25mm	No	4.95	Rupees Four and Ninety Five Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92